	Tender No Package Name	NETC/Ghy/OTE/O&M/TLSA/2022-23/15 Supply, Supervision of Installation & Commissioning of Transmission Line Surge Arrestors (TLSA) for 400 kV D/C Silchar-Byrnihat -Azara - Bongaigaon Transmission Line		Amendment-01
	TECHNICAL			
Sr No.	Clause Description	Specification	As per Existing Bid Document	As Amended
1	Clause 3.0 Sr. No. d) Page 4 of 13	CONSTRUCTIONAL FEATURES	Seals shall be provided in such a way that these are always effectively maintained even when discharging rated lightning current. There shall be no extra holes on the TLSA so as to disallow moisture ingress.	Separate Sealing arrengment shall not be required.
2	Clause 4.0 Sr. No. c) Page 4 of 13	FITTINGS AND ACCESSORIES	Suspension clamp assembly shall be provided with Aluminium clamp, galvanized steel clamp straps. Suspension clamp shall be suitable for conductor (twin moose ACSR conductor 400kV) range from 9.5 to 65 mm diameter. Galvanized steel line palm with M20x55 min full thread shall be provided. M12 connectoin shall be there on galvanized steel palm for shorting copper braid/cable (of min. 50mm width)	Suspension clamp assembly shall be provided with Aluminium clamp, galvanized steel clamp straps. Suspension clamp shall be suitable for conductor (twin moose ACSR conductor 400kV-horizontal arrangement) range from 9.5 to 65 mm diameter. Galvanized steel line palm—shall be provided. The lugs provided should be sutiable for Tower end existing hole of 17.5mm.
3	Clause 5.0 Sr. No. (c) Page 5-6 of 13	Routine Tests	5. Sealing test: water dip test at 1.5m depth from top for 30 minutes during assembly of stacks(followed by other routine test i.e., PD measurement, reference voltage, residual voltage & IR measurement).	5. Sealing test: - As per IEC 60099-4, it is not part of routine test.

4	Page 8 of 13	Drawing	1) Arrester height 4355 +/- 75mm 2) Top height 235 mm 3) Cu braid strip 50mm width approx 450 mm	The attached drawing is only for informative, the height of TLSA shall be suitable for 420kV as per bidders own design, preferrably POWERGRID tested and approved.
5	Page 7 of 13 Sr. No. 3	Basic Technical Specificaiton of 400kV	No. of units per arrester - 3 units of 140kV each	No. of units per arrester - units shall depends on bidders design.
6	Page 7 of 13 Sr. No. 9	Basic Technical Specificaiton of 400kV TLSA	Maximum continuous operating voltage - 330 kV rms	Maximum continuous operating voltage - 336kV rms.
7	Page 7 of 13 Sr. No. 11	of 400kV TLSA	Maximum steep current Impulse Residual Voltage at 10KA of 1 micro sec from Time- 1275 kVpeak	Maximum steep current Impulse Residual Voltage at 10KA of 1 micro sec from Time-less than 1275 kV peak.
8	Page 7 of 13 Sr. No. 13	Basic Technical Specificaiton of 400kV TLSA	Minimum energy discharge capability-5kJ/kV (OD)	Minimum energy discharge capability- 4.5kJ/kV (OD)
9	Page 7 of 13 Sr. No. 17 i)	Basic Technical Specificaiton of 400kV TLSA	Resistive current- less than 200 microAmp.	Resistive current- less than 800 microAmp.
10	Page 7 of 13 Sr. No. 17 ii)	Basic Technical Specificaiton of 400kV TLSA	Capacitive current- about 1400 microAmp.	Capacitive current- about 1300 microAmp.
11	Page 7 of 13	Disconnector Detials	1) Rated Energy - 4 kJ/kV 2) Rated charge - 1 coulomb 3) Mechanical Strength - 3kN(Pull test) 4) Operating Time - ≤10 ms	1) Rated Energy - 4 kJ/kV 2) Rated charge - 1 coulomb 3) Mechanical Strength - 3kN(Pull test) 4) Operating Time - ≤12 ms

12	Page 10 of 13	Manufacturin Quality Plan	Section-1	1) Raw material & brought out components -
12	1 460 10 01 10	Triandiactum Quanty man	1) Raw material & brought out components	Many parameters are not performed/tested at
			2) ZnO block	RRL. It is verified through supplier TCs.
			3) Metal fittings	2) ZnO block - Only visual & dimension check
			4) Heat Sink	and other electrical test are verified through
			5) FRP rod	TCs
			6) Fastners/Hardware	
				3) Metal fittings – For "Chemical
			7) Machining components	Composition" - verification of supplier TC
			8) Brackets & DD5 Disconnector	4) Heat sink – For "Chemical Composition" –
				verification of supplier TC 5)FRP rod – For Tg
				& glass content – verification of supplier TC
				6) Hardware/Fasteners – For "chemical composition" – verification of supplier TC
				7) Machining component - For "chemical
				composition" – verification of supplier TC.
				Material test certificates shall be submitted for
				review and internal report shall also be
				submitted for review.
				MTC of raw materials and Test certificate to
				be submitted.
				be submitted.
	COMMERCIAL			
12	Request For Proposal		Bid Receipt Time & Date:	Bid Receipt Time & Date:
			Upto 15:00 Hrs. on 08.12.2022	Upto 15:00 Hrs. on 23.12.2022
				Bid Opening Time & Date:
				Upto 15:30 Hrs. on 23.12.2022
13		Scope of Work	"Design, Manufacture, Assembly, Factory Testing,	"Design, Manufacture, Assembly, Factory
	Contract (SCC), clause		Packing, Forwarding, Transportation, Transit	Testing, Packing, Forwarding, Transportation,
	no. 2.1, page no.24		Insurance, Supply, Delivery, Supervision of	Transit Insurance, Supply, Delivery,
			Installation and Commissioning of Transmission	Supervision of Installation and Commissioning
			Line Surge Arrestors (TLSA) for 400 kV D/C	of Transmission Line Surge Arrestors (TLSA)
			Silchar-Byrnihat -Azara -Bongaigaon	for 400 kV D/C Silchar-Byrnihat -Azara -
			Transmission Line, including all clamps &	Bongaigaon Transmission Line, including all
			connectors, dis-connectors, insulated flexible	clamps & connectors, dis-connectors,
1			copper connecting cables of requisite size &	insulated flexible copper connecting cables of
1	1		length, Surge monitors, all other accessories as	requisite size & length, all other accessories as
			required".	required".

14	Special Conditions of Contract (SCC), clause no. 5.0, page no.27	l ±	l ' ' ' '	The entire supplies shall have to be made within 5 Months (150 days) from the date of firm order.
15	Special Conditions of Contract (SCC), clause no 9.2, page 29		successful commissioning of the Transmission line LAs and issuance of TOC (Taking over certificate) by concerned Engineer-In-Charge.	Balance 30% payment shall be released after successful commissioning of the Transmission line LAs and issuance of TOC (Taking over certificate) by concerned Engineer-In-Charge or within 240 days from the date of issuance of TOC, whichever is earlier.